



PALACIO DEL GOBERNADOR

CONDOMINIUM CORPORATION

(A Non-Stock and Non-Profit Organization)

Gen. Juna St., cor. A. Soriano Jr. Ave., Intramuros Manila

Telefax No.559-911-9 ; Web page: www.pdgcc.gov.ph

e-mail: palaciodelgobernador@ymail.com

REQUEST FOR QUOTATION

The Palacio del Gobernador Condominium Corporation will undertake a Small Value Procurement for the Installation of 4 Step Capacitor Bank Rated 60KVAR, 480Volts in accordance with Section 53.9 of the Implementing Rules and Regulations of Republic Act No. 9184.

Name of Project : Supply of Manpower, Materials, Tools/Equipment and Engineering Supervision for the Installation of 4 Step Capacitor Bank Rated 60KVAR, 480 Volts.

Approved Budget for the contract : P656, 250.00

Specification : See attached Annex "A"


Location : Basement, Palacio del Gobernador Cond. Corp., A. Soriano Ave. cor. General Luna St. Intramuros, Manila.

Delivery Period : 4 weeks

Submission of quotation and eligibility documents is on or before September 16, 2019 at the Administration Office, Basement, Palacio del Gobernador Cond. Corp., A. Soriano Ave. cor. General Luna Street, Intramuros, Manila. Open submission may be submitted, manually or through facsimile.

For inquiry, you may contact us at Tele Fax No 559-9119.

Very truly yours,


ATTY. RAYMUNDO U. TAN
OIC Administrative Committee
Bureau of the Treasury
Chairman, PDGCC Administrative Committee

SCOPE OF WORK:

1. Mobilization of manpower and equipment
2. Preventive Maintenance of the system;
3. Removal of under rated main circuit breaker;
4. Installation of new magnetic contactor 3P, 480V;
5. Removal and Replacement of busted pilot lights;
6. Retrofitting, replacement and fabrication of 3/8 x 3 copper busbar;
7. Fabrication of New Air Circuit Breaker channel and support;
8. Fitting and installation of New 1500Amp, 3P, 600V chassis;
9. Installation of New 1500Amp, 3P, 600V max Air Circuit Breaker;
10. Installation of capacitor bank line side feeder cable;
11. Cleaning of project job site;
12. Testing and Commissioning.

MATERIALS:

QTY.	UNIT	DESCRIPTION
1	pc.	1500 3P, 460V, 3Ø
4	pcs.	100Amp. 3P, 460V 3Ø
12	pcs.	20KVAR, 460V, 3Ø Capacitor
1	pc.	Mikron Capacitor Bank Controller
40	pcs.	Pilot Lights
2	pcs.	Boy THHN Wire #14
4	pcs.	125Amp. 3Ø, 60Hz Magnetic Contactor
1	Lot	Busbar Assy
1	pc.	Angle Bar 3x3x20 standard
1	pc.	C Channel 2x3x20 standard
9	pcs.	3x50mm Terminal Lugs
1	Lot	Consumable Materials
1	Lot	Supply of labor, tools, equipment, engineering supervision for the installation of additional capacitor and circuit breaker.